

DAL3 is a 13.2K SQFT facility located in the renowned Infomart building at 1950 North Stemmons Freeway. With enterprise-grade infrastructure at the most densely connected interconnection site in the region, DAL3 is ideally located for primary IT deployments that require 100% uptime and reliable network performance.

### **Unrestricted Connectivity**

Through direct access to the Meet-Me-Room, DAL3 provides network-neutral access to 55+ unique networks as well as a robust ecosystem including major cloud providers such as Microsoft® Azure ExpressRoute and Amazon Web Services®.

# Superior Power, Security and Redundancy Solutions

With 2N redundancy on UPS from three different utility substations using two automatic transfer switches (ATSs), two back-up generators and redundant cooling systems, the Cologix DAL3 facility offers unparalleled resiliency, redundancy and security compliance including SOC 1, SOC 2, HIPAA and PCI-DSS.

# **Why Cologix Dallas?**

Located in the Infomart building, the region's preeminent carrier hotel, DAL3 provides diverse, unfettered connectivity to 55+ networks and access to abundant fiber in the region via a Meet-Me-Room. Ideally situated at the major crossroads of network connectivity in the south-central United States, the Dallas data center site is perfect for primary IT deployments or latency-sensitive applications. Choosing DAL3 includes the ease of doing business with Cologix.

### **Data Center Quick Facts**

- 55+ unique networks in the Meet-Me-Room, including into Central America
- Independent third-party assessments for SOC 1, SOC 2, HIPAA, and PCI-DSS
- ISO 27001 certified by Schellman

- Access to the largest number of carriers out of any single building in a 900-mile radius
- Low environmental risks, attractive tax incentives and low energy costs

# Cologix by the Numbers

40+
Data centers

Markets in North America

29
Onramps

600+

19,000+
Interconnections

# Site Specifications DAL3: 1950 N. Stemmons Freeway, Suite 1032, Dallas, Texas

#### **Site Information**

Site Capacity — 1.6 MW

Site Type — Purpose build data center

DC Space — 13.2K SQFT

Building — 7-story office building, concrete & steel

Data Halls — 1

Rack Size Up To  $\,-\,$  48 RU

Space Configuration — 24" x 48" cabinets, custom cages

# **Security**

Cameras — Dual DVRs with 90-day retention/CCTV

Access — Biometric and badge access 24/7/365, Mantraps

Security Personnel — 24/7/365

#### **Environmental Controls**

Cooling — 300+ tons N+1 coolers, controls and perimeter cooling

Fire Suppression — N2 fire suppression, VESDA and smoke detection

Fuel Storage — 48 hours run time with three fuel contracts, two local and one national

#### **Power**

Generator + UPS — 2N uninterruptible power system, UPS generator

Load Design — Up to 15 kW/cabinet for high density

Power Usage Effectiveness (PUE) — 1.5

## Connectivity

Meet-Me-Room (MMR) — 1 Cologix controlled in DAL1 with diverse paths to DAL2 and DAL3

Networks — 55+ unique networks

Fiber Entrance — Basement vaults by individuals' carriers to controlled Cologix vault

Point of Entry (POE) — 4 power priority hospital grade feeds from 3 diverse utility substations